Name of Work:- Providing chambers to existing borewell and consealing to road surface area in ward no 13 shettihalli sub - division

Royalty Statement

Sl No	Description of Item	Unit	Aggregate/Size stone			Sand/Gravel		
			Qty	Constant	Quantity	Qty	Constant	Quantity
1	PCC 1:3:6	Cum	5.74	0.69	3.96	5.74	0.56	3.21
3	RCC M25	Cum	30.52	0.69	21.06	30.52	0.46	14.01
3	RCC Slabs	Cum	9.56	0.69	6.60	9.56	0.46	4.39
	Total				**31.62**	**Total**		**21.61**

Abstract

Sl No	Description of materials	Unit	Quantity	Rate / Cum (Rs)	Amount		
1	Aggregate	Cum	31.62	126.00	3984.12 / 3983.90		
2	Sand/Dust	Cum	21.61	138.00	2982.52 / 18		
				Total	**6966.42**		

Assistant Engineer
Ward No.12
BBMP, Bengaluru

Assistant Executive Engineer
Shettyhalli Sub Division
BBMP, Bengaluru